

Letter No.: BSEIDC / ARCH/08/2011-3292

Date: 24.04.15

**Corrigendum No.01**

**(DIET Building)**

- 1) **DIET Institutional Building:** Provision of Kota Stone slab flooring and skirting (as per SOR No..11.48.1 and 11.49) instead of 40 mm thick marble chips flooring and skirting rubbed and polished to granolithic finish (as per SOR No..11.16.2 , 11.18.2.2 and 11.20.1)
- 2) **DIET Girl's/Boy's Hostel Building:** Provision of Kota Stone slab flooring and skirting (as per SOR No..11.48.1 and 11.49) instead of cement concrete flooring (1:2:4) finished with a floating load as need cement including cement slurry etc. (as per SOR No..11.4.2)
- 3) **DIET Principal Quarter:** Provision of Kota Stone slab flooring and skirting (as per SOR No..11.48.1 and 11.49) instead of cement concrete flooring (1:2:4) finished with a floating load as need cement including cement slurry etc. (as per SOR No..11.4.2)

  
(Brajesh Prasad)  
Chief Engineer,  
BSEIDC Ltd., Patna